
## **PRODUCT DATA SHEET**

Sea Water Reverse Osmosis (SWRO) System

## **OVERVIEW**

Our Sea Water Reverse Osmosis (SWRO) plants are designed to treat water, with < 35,000 mg/L of dissolved solids (TDS) and < 10 mg/L of suspended solids (TSS), to achieve potable water quality. The standard treatment process involves pre filtration (auto backwashing multimedia filters and cartridge filters), anti-scalant dosing to prevent membrane scaling, RO desalination and auto flushing and CIP systems for membrane cleaning. Additional pre-RO and post-RO treatment steps may be added as required to suit feed water conditions and/or treated water quality requirements. Our SWRO plants are available as skid mounted or containerised systems.





## STANDARD SPECIFICATIONS

Parameter	Units	SWRO-1	SWRO-2	SWRO-3	SWRO-4	SWRO-5	SWRO-6	SWRO-7	SWRO-8	SWRO-9	SWRO-10
Permeate Flow Rate	m³/d	10	20	30	40	50	60	70	80	90	100
Permeate Recovery Rate	%		40 - 45								
Permeate TDS	mg/L	< 250									
Raw Water TDS	mg/L	< 35,000									
Raw Water TSS	mg/L	< 10									
Raw Water Temperature	°C		15 ~ 30								
Ambient Design Temperature	°C		15 ~ 30								
RO Water Inlet Pressure	bar		3 - 4								
RO Unit High Pressure	bar	40 - 60									
RO Brine Discharge Pressure	bar	25 - 35									
Power Supply	-	380~450 V, 3 Phase, 50/60 Hz									

## **STANDARD INCLUSIONS + OPTIONS**

Equipment		SWRO-1	SWRO-2	SWRO-3	SWRO-4	SWRO-5	SWRO-6	SWRO-7	SWRO-8	SWRO-9	SWRO-10
Skid Mounted Plant & Equipment		1	1	1	1	1	1	1	1	1	1
Low Pressure Feed Pump		1	1	1	1	1	1	1	1	1	1
High Pressure RO	Std Efficiency	1	1	1	1	1	1	1	1	1	1
Pump (c/w ERD)	High Efficiency	-	0	0	0	0	0	0	0	0	0
	Sand Filter	1	1	1	1	1	1	1	1	1	1
Pre-filtration	Ultra Filtration	0	0	0	0	0	0	0	0	0	0
	Activated Carbon	0	0	0	0	0	0	0	0	0	0
	Cartridge Filters	1	1	1	1	1	1	1	1	1	1
Anti Scalant Dosing System		1	1	1	1	1	1	1	1	1	1
Membrane CIP & Auto Flush System		1	1	1	1	1	1	1	1	1	1
PLC Control System with HMI		1	1	1	1	1	1	1	1	1	1
Container with Insulation & climated		0	0	0	0	0	0	0	0	0	0
Additional Post-RO Treatment		0	0	0	0	0	0	0	0	0	0
Premium Instrumentation Package		0	0	0	0	0	0	0	0	0	0
Permeate Distribution Pump Set		0	0	0	0	0	0	0	0	0	0

Instrumentation	Standard Package				
Pressure Gauges	1				
Pressure Transmitters (4-20 mA)	0				
HP RO Pump Inlet Low Pressure Switch	✓ <i>✓</i>				
Flow Gauges (Rotameters)	1				
Flow Transmitters (4-20 mA)	0				
Conductivity Transmitter (4-20 mA)	1				
Float Switches (Feed/Permeate, Chemical Dosing & CIP Tanks)	✓ ✓				
Remote Monitoring & Control Capabilities	0				

\*\*\* Installation and transportation fee is not included in the stated prices. We will charge 2 technicians and 1 engineer for installation and start-up operations of treatment system. Installation and start-up fee is 500 \$/day for each person.

\*\*\* CUSTOMER will pay for traveling-visa (Istanbul – Site in XXX – Istanbul), accommodation and food fees for our personnel during site work



